

SCHEDULE - A

Name of work : Major Conservation to the 1st Granary at Arulmigu Aranganatha swamy temple, Srirangam.

Value of Contract Rs. 11,62,170.00/-

Date of tender : 27.02.2015

Issued to :

EMD : Rs. 11,700/-

Time for Completion: 2 months

JOINT COMMISSIONER / EXECUTIVE OFFICER.

SI No	Probable Quantity	Description of work	TNDSS No.	Rate quoted by Contractors		Unit	Amount
				in words	Figures		
1	725.00 Cubic Metre	Excavating the accumulated / filled earth in and around the granary to expose the original structure of the ancient granary and disposing the earth to a far off place etc, complete including conveyance charges of debris to distance of 5km outside of temple premises.				1m ³ (one cubic metre only)	
2	4.00 Cubic Metre	Dismantling the supporting stone wall on eastern side of the granary to expose the original structure of the granary.				1m ³ (one cubic metre only)	
3	438.00 Square Metre	Clean removal of the existing dead lime mortar plastering over the granary wall and racking out the brick joints etc, complete including conveyance charges of debris to distance of 5km outside of temple premises.				1m ² (one square metre only)	
4	6.00 Cubic Metre	Dismantling the cracked and out of plump brick wall of the granary and disposal of debris etc complete including conveyance charges of debris to distance of 5km outside of temple premises.				1m ³ (one cubic metre only)	
5	34.00 Cubic Metre	Mending / Underpinning the bottom portion of the granary wall with similar type of bricks in Combination Mortar 1:1:3, curing etc, complete including cost and conveyance of all materials and all labour charges, including grinding charges for combination mortar hire charges for grinding machine and tools etc, conveyance to site.				1m ³ (one cubic metre only)	

Contractor

No. of Corrections :

No. Over Writing :

Joint Commissioner / Executive Officer

6	6.00 Cubic Metre	Reconstruction of IIIrd Tier of granary wall with similar type of bricks in Combination Mortar 1:1:3 curing, etc complete including cost and conveyance of all materials and all labour charges, including grinding charges for combination mortar hire charges for grinding machine and tools etc, conveyance to site.				1m ³ (one cubic metre only)	
7	438.00 Square Metre	Replastering the brickwall of the granary with Combination Mortar 1:1:5, 20mm thick including curing etc complete including cost and conveyance of all materials and all labour charges, including grinding charges for combination mortar hire charges for grinding machine and tools etc, conveyance to site.				1m ² (one square metre only)	
8	438.00 Square Metre	Applying thin coat of hand grinded lime mortar paste (Theervai) over the newly plastered surface as per the existing style and glues including curing, etc complete including conveyance charges of debris to distance of 5km outside of temple premises.				1m ² (one square metre only)	
9	1.00 Item	Supplying and fixing of new Teak wood beam and pillar of 1.47m ³ and joists of 0.614m ³ in the missing place of the roof and inner portion of granary including painting two coats over one coat of primer etc, complete on directed by the departmental officer including cost and conveyance of all materials and all labour charges etc, complete.				1 item (one item only)	
10	48.00 Square Metre	Redoing the fallen Terraced roofing of the granary with brick on edge, 125mm concrete, 2 course of flat tiles and one coat of plaster 15mm thick to the bottom including cost and conveyance of all materials and all labour charges etc, complete.				1m ² (one square metre only)	
11	31.00 Square Metre	Relaying of brick flooring with bricks over the brick jelly lime concrete and pointing the bricks joints including cost and conveyance of all materials and all labour charges etc, complete.				1m ² (one square metre only)	

12	8.00 Square Metre	Supplying and fixing of new teak wood doors and windows to granary including painting etc, complete including cost and conveyance of all materials and all labour charges etc, complete.				1m ² (one square metre only)	
13		Dismantling the cloister mandapam adjacent to the granary in southern side of granary					
	26.00 Cubic Metre	a) Dismantling weathering course including conveyance charges of debris outside the temple complex etc, complete.				1m ³ (one cubic metre only)	
	62.62 Square Metre	b) Dismantling ceiling slabs over the mandapam and bringing item source including erection of scaffolding etc, complete.				1m ² (one square metre only)	
	12.00 Nos	c) Dismantling Beam over the roof and bringing item and stacking item etc, complete.				1No (Each)	
	8.00 Nos	d) Dismantling the capital cloister mandapam etc, complete.				1No (Each)	
	12.00 Nos	e) Dismantling pillars and stacking them in over etc complete.				1No (Each)	
14	171.00 Cubic Metre	Clearance of cowdung/ manure stacked near by the granary to keep the place in a neat and tidy condition.				1m ³ (one cubic metre only)	
15	18.00 Cubic Metre	Dismantling the stone wall of Thirumadil for movement of vehicles (Temporarily) for conveyance of materials from the work spot of granary.				1m ³ (one cubic metre only)	
16	10.00 Cubic Metre	Dismantling core inbetween veneer stones of Thirumadil work etc, complete.				1m ³ (one cubic metre only)	
17	8.00 Cubic Metre	Reconstruction of stone wall with Combination mortar 1:1:3 and pointing the stone joints with CM 1:1:3 including conveyance and labour and curing etc, complete.				1m ³ (one cubic metre only)	

18	10.00 Cubic Metre	Filling core inbetween veneer stones with country bricks/special bricks in Combination mortar 1:1:5 including cost and conveyance of all materials and labour charges including curing etc, complete.				1m ³ (one cubic metre only)	
19	450.00 Square Metre	Scaffolding charges for vimanams and gopurams with cosurina post, coconut or palm trees wherever necessary for main, form work and providing with coconut keeth coverings, providing ladder arrangements, country wood plank for working, inspections etc., complete hire charges only for erection, maintenance and removing the same on completion of works.				1m ² (one square metre only)	

Contractor

No. of Corrections :
No. Over Writing :

Joint Commissioner / Executive Officer