

SCHEDULE - A

Name of work : Major Conservation to 2nd Granary at Arulmigu Aranganatha swamy temple, Srirangam.

Value of Contract Rs. 9,81,399.00/-

Date of tender : 27.02.2015

Issued to :

EMD : Rs. 9,900/-

Time for Completion: 2 months

JOINT COMMISSIONER / EXECUTIVE OFFICER.

SI No	Probable Quantity	Description of work	TNDSS No.	Rate quoted by Contractors		Unit	Amount
				in words	Figures		
1	20.00 Cubic Metre	Excavating the accumulated / filled earth in and around the granary to expose the original structure of the ancient granary and disposing the earth to a far off place etc, complete including conveyance charges of debris to distance of 5km outside of temple premises.				1m ³ (one cubic metre only)	
2	438.00 Square Metre	Clean removal of the existing dead lime mortar plastering over the granary wall and racking out the brick joints etc, complete including conveyance charges of debris to distance of 5km outside of temple premises.				1m ² (one square metre only)	
3	20.00 Cubic Metre	Dismantling the cracked and out of plump brick wall of the granary and disposal of debris etc complete including conveyance charges of debris to distance of 5km outside of temple premises.				1m ³ (one cubic metre only)	
4	34.00 Cubic Metre	Mending / Underpinning the bottom portion of the granary wall with similar type of bricks in Combination Mortar 1:1:3, curing etc, complete including cost and conveyance of all materials and all labour charges, including charges for combination mortar have charges for grinding machine and tools etc, conveyance to site.				1m ³ (one cubic metre only)	
5	20.00 Cubic Metre	Reconstruction of Illrd Tier of granary wall with similar type of bricks in Combination Mortar 1:1:3 curing, etc complete including cost and conveyance of all materials and all labour charges, including charges for combination mortar have charges for grinding machine and tools etc, conveyance to site.				1m ³ (one cubic metre only)	

Contractor

No. of Corrections :

No. Over Writing :

Joint Commissioner / Executive Officer

6	438.00 Square Metre	Replastering the brickwall of the granary with Combination Mortar 1:1:5, 20mm thick including curing etc complete including cost and conveyance of all materials and all labour charges, including charges for combination mortar have charges for grinding machine and tools etc, conveyance to site.				1m ² (one square metre only)	
7	438.00 Square Metre	Applying thin coat of hand grinded lime mortar paste (Theervai) over the newly plastered surface as per the existing style and glues including curing, etc complete including conveyance charges of debris to distance of 5km outside of temple premises.				1m ² (one square metre only)	
8	1.00 Item	Supplying and fixing of new Teak wood beam and pillar of 1.47m ³ and joists of 0.614m ³ in the missing place of the roof and inner portion of granary including painting two coats over one coat of primer etc, complete on directed by the departmental officer.				1 Item (one item)	
9	48.00 Square Metre	Redoing the fallen Terraced roofing of the granary with brick on edge, 125mm concrete, 2 course of flat tiles and one coat of plaster 15mm thick to the bottom including cost and conveyance of all materials and all labour charges etc, complete.				1m ² (one square metre only)	
10	31.00 Square Metre	Relaying of brick flooring with special bricks over the brick jelly lime concrete and pointing the bricks joints including cost and conveyance of all materials and all labour charges etc, complete..				1m ² (one square metre only)	
11	8.00 Square Metre	Supplying and fixing of new teak wood doors and windows to granary including painting including cost and conveyance of all materials and all labour charges etc, complete.				1m ² (one square metre only)	
12	450.00 Square Metre	Scaffolding charges for vimanams and gopurams with cosurina post, coconut or palm trees wherever necessary for main, form work and providing with inflammable materials coverings, providing ladder arrangements, country wood plank for working, inspections etc., complete hire charges only for erection, maintenance and removing the same on completion of works.				1m ² (one square metre only)	