

SCHEDULE - A

Name of work : Special Repairs to North West Mugamandapam of 1000 Pillar Mandapam of A/m. Aranganathaswamy temple, Srirangam.

Value of Contract Rs. 30,46,963.00/-

Date of tender : 27.02.2015

Issued to :

EMD : Rs. 30,500/-

Time for Completion: 2 months

JOINT COMMISSIONER / EXECUTIVE OFFICER.

SI No	Probable Quantity	Description of work	TNDSS No.	Rate quoted by Contractors		Unit	Amount
				in words	Figures		
1	99.00 Square Metre	Dismantling of weathering course and disposing the same to outside the temple premises etc, complete.				1m ² (one square metre only)	
2	26.40 Square Metre	Dismantling the ceiling slabs and stacking them properly for reuse etc, complete.				1m ² (one square metre only)	
3	26.40 Square Metre	Reerrection of ceiling slab in position including erection and dismantling of scaffolding etc, complete.				1m ² (one square metre only)	
4	1.00 Item	Providing proper prop.(support) to the Mandapam for safty and security with Tubler scaffolding, sand Bag etc, complete.				1Item (one item only)	
5	2.00 Nos	Dismantling the broken lintel beam of size 2.60m x 0.70m x 0.45m and bringing them down including erection of scaffolding etc, complete.				1No (Each)	
6	2.00 Nos	Making, Supplying and fixing of new stone beam of size 2.60m x 0.70m x 0.45m as per the existing style and glues including erection of scaffolding etc, complete.				1No (Each)	
7	1.00 No	Dismantling the cracked beam of size 2.60m x 0.20m x 0.30m and bringing them down including erection of scaffolding etc, complete.				1No (Each)	

Contractor

No. of Corrections :

No. Over Writing :

Joint Commissioner / Executive Officer

8	1.00 No	Making, Supplying and fixing of new tie beam of size 2.60m x 0.20m x 0.30m as per the existing style and glues including erection of scaffolding etc, complete.				1No (Each)	
9	36.70 Cubic Metre	Dismantling the out of plumb ornamental Adhishtana moulding stones and stacking them in order for reuse including numbering, erection of scaffolding etc, complete.				1m ³ (one cubic metre only)	
10	39.30 Cubic Metre	Reconstruction of ornamental Adhishtana portion with combination mortar 1:1:4 and pointing the stone joints with combination mortar 1:1:3, curing etc, complete.				1m ³ (one cubic metre only)	
11	90.00 Square Metre	Dismantling of damaged and undulated stone flooring and disposing the same to far off place etc, complete.				1m ² (one square metre only)	
12	90.00 Square Metre	Laying of new stone flooring over a bed of Brick jelly concrete in lime and set in Combination Mortar 1:1:4 and pointing the stone joints with Combination Mortar 1:1:3 curing etc, complete.				1m ² (one square metre only)	
13	29.50 Running Metre	Dismantling the ornamental chajja over the roof and stacking them for reuse including erection of scaffolding etc, complete.				1Rmt (one running metre only)	
14	7.50 Running Metre	Making and supplying of new ornamental stone chajja as per the existing style and glues including cost of stone and labour charges etc, complete.				1Rmt (one running metre only)	
15	29.50 Running Metre	Refixing of ornamental chajja over the roof and set in combination mortar 1:1:4 etc, complete.				1Rmt (one running metre only)	
16	1125.00 Square Metre	Pointing the stone joints with combination mortar 1:1:3 including racking out the existing dead mortar etc, complete.				1m ² (one square metre only)	

17	60.00 Nos	Mending and strengthening of erroded bottom portion of the pillars with quarry dust, Stone chips and epoxy etc, as per the existing design including cleaning the surface etc, complete.				1No (Each)	
18	1.00 Item	Carefully removing the Brick masonry around the bottom portion of the pillar after given proper support to the roof of the Mandapam etc, complete.				1Item (one item only)	
19	94.00 Square Metre	Providing apron around the Mugamandapam (N.W of 1000 pillar Mandapam) with available old stones over a bed of Brick jelly concrete in lime to prevent water percolation in to the core.				1m ² (one square metre only)	
20	20.00 Nos	Providing skylight opening of size 2.54m x 0.60m over the ceiling portion to rear side of 1000 pillar Mandapam including dismantling weathering course, ceiling slab and cleaning the debris construction of brick parapet 23cm thick opening to a height of 60cm with combination mortar 1:1:3 and plastering 20mm thick with combination mortar 1:1:5 fixing S.S.rods for opening as directed by departmental officers etc, complete.				1No (Each)	
21	1.00 Item	Digging carefully upto upana (off set) to expose the Adhishtana moulding including stone wheel and horses located at the centre of the 1000 pillar Mandapam etc, complete.				1Item (one item only)	
22	115.00 Kilo Gram	Supplying and fixing of S.S.Grill of approved design with grill work for opening using 1¼"x1¼" square pipes around and 1"x1" S.S. weld mesh inner to hight of 75cm and should be fixed with fibre material in between pillars etc, complete.				1kg (one kilo gram only)	

23	99.00 Square Metre	Laying of weathering course for the Mandapam roof by laying brick jelly concrete in pure lime and laying one course of Pressed Tiles of size 23 x 23 x 2cm with Combination Mortar 1:1:4 and pointing the joints with Combination Mortar 1:1:3 including curing etc, complete.				1m ² (one square metre only)	
24	66.00 Cubic Metre	Dismantling of Brick/Stone parapet and disposing the same from inside the temple premises to outside for disposal etc, complete.				1m ³ (one cubic metre only)	
25	15.00 Cubic Metre	Reconstruction of Brick parapet wall using spl.type of Bricks over the roof of the Mandapam with combination mortar 1:1:4 including curing etc, complete.				1m ³ (one cubic metre only)	
26	79.00 Square Metre	Plastering the Brick parapet wall with combination mortar 1:1:5,20mm thick including erection of scaffolding curing etc, complete.				1m ² (one square metre only)	
27	2.00 Nos	Mending the out of plumb and dislodged elephant stone sculpture newly exposed on both sides of North west Mugamandapam of 1000 pillar Mandapam etc, complete.				1No (Each)	
28	2.00 Nos	Carefully opening of the existing irregular crack of the pillar bottom and refilling with quarry dust and epoxy mixer etc, complete.				1No (Each)	
29	42.00 Nos	Filling the holes drilled in the pillar (core) in the past for fixing iron grill with quarry dust and epoxy mixer etc, complete .				1No (Each)	
30	1.00 Item	Proper packing with stone chips of the existing cavities in between lintel beam and ceiling slabs and pointing with combination mortar wherever necessary at 1000 pillar Mandapam.				1Item (one item only)	

31	4356.00 Cubic Metre	Earth work excavation for cleaning the filled / accumulated earth inbetween N.W. Mugamandapam of 1000 pillar Mandapam and Thirumadil wall to expose the Adhishtana portion.				1m ³ (one cubic metre only)	
32	14.20 Cubic Metre	Laying foundation concrete P.C.C 1:4:8 using 40mm stone jelly curing etc, complete.				1m ³ (one cubic metre only)	
33	50.00 Cubic Metre	Construction of flight stone masonry steps from upana level upto Mandapam with combination mortar 1:1:4 and pointing the stone joints with C.M. 1:1:3 including erection of scaffolding etc, complete.				1m ³ (one cubic metre only)	
34	322.00 Kilo Gram	Supplying and fixing of S.S.Grill Railing of approved design with grill work for opening using 1¼"x1¼" square pipes around and 1"x1" S.S. weld mesh inner to height of 80cm and should be fixed with the grill over the sides of steps including making holes over the stones etc, complete.				1kg (one kilo gram only)	