

SCHEDULE - A

Name of Work:

Repairs and renovation to Rampart wall (Thirumathil) 7th enclosure in between East Adayavalanjan street and Drainage road in connecting North East Corner to East Mottai Gopuram to a length of 383.54m in A/m. Aranganatha swamy Thirukoil, Srirangam.

Value of Contract Rs. 44,04,785/-

Date of tender : 10.01.2016

Issued to :

EMD : Rs. 45000/-

Time for Completion: 6 Months

JOINT COMMISSIONER / EXECUTIVE OFFICER.

SI No	Probable Quantity	Description of work	TNDSS No.	Rate quoted by Contractors		Unit	Amount
				in words	Figures		
1	2	3	4	5	6	7	8
1	45.00 (forty five cubic metre)	Dismantling Cut stone Masonry in lime mortar, clearing away and carefully stacking materials useful for reuse including conveyance of materials to road side, labour charges and head load with necessary lead and lift charges etc., complete.				1m ³ (one cubic metre only)	
2	1250.00 (one thousand two hundred fifty square metre)	Clean removal of existing lime mortar plaster to a thickness 20mm by racking out joints including conveyance of materials to road side, labour charges and head load with necessary lead and lift etc., complete.				1m ² (one square metre only)	
3 a)	45.00 (forty five cubic metre)	Reconstruction of Cut stone Masonry using available old Cut stones in combination mortar 1:1:4 (one part of cement, one part of lime and four parts of sand) including conveyance of all materials to site of work and head load with necessary lead and lift, etc., complete.				1m ³ (one cubic metre only)	
3 b)	51.00 (fifty one square metre)	Labour charges for Palamuna dressing for cut stone Masonry including dressing charges for all sides, cost of smithy materials, charcoal etc., and labour charges for preparation of smithy materials such as sharpening of uli etc., but excluding cost of cut stone etc, complete.(Measurement for payment will be taken for front face area only)				1m ² (one square metre only)	

Contractor

No. of Corrections :

No. Over Writing :

Joint Commissioner / Executive Officer

1	2	3	4	5	6	7	8
3 c)	14.00 (fourteen cubic metre)	Construction of Cut stone Masonry in combination mortar 1:1:4 (one part of cement, one part of lime and four parts of sand) using new dressed stones including cost and conveyance of all materials, labour charges and head load with necessary lead and lift etc, complete.				1m ³ (one cubic metre only)	
4	67.00 (sixty seven cubic metre)	Core filling with new Soling stones in combination mortar 1:1:4 (one part of cement, one part of lime and four parts of sand) including cost and conveyance of all materials and labour charges and head load with necessary lead and lift, etc, complete.				1m ³ (one cubic metre only)	
5	3470.00 (three thousand four hundred seventy square metre)	Providing two legged scaffolding arrangements to the required height using M.S. Pipe posts for verticals and Horizontals, including couplers, base plates, longitudinal, transverse and middle braces and providing a platform with country wood planks of required width and thickness to suit for site and design requirement etc, complete.				1m ² (one square metre only)	
6	53.00 (fifty three cubic metre)	Providing Weathering course using 20mm brick jelly with lime the proportion of brick jelly to lime being 32 : 12½ cft including cost and conveyance of all materials to site of work labour charges and head load with necessary lead and lift etc, complete.				1m ³ (one cubic metre only)	
7	1761.00 (one thousand seven hundred sixty one square metre)	Plastering with combination mortar 1:1:4 (one part of cement, one part of lime and four parts of sand) - 20mm thick including cost and conveyance of all materials, labour charges and head load with necessary lead and lift etc, complete.				1m ² (one square metre only)	

1	2	3	4	5	6	7	8
8	3468.00 (three thousand four hundred sixty eight square metre)	Pointing with combination mortar 1:1:4 (one part of cement, one part of lime and four parts of sand) - 10mm thick including cost and conveyance of all materials, labour charges for racking the joints and head load with necessary lead and lift etc, complete.				1m ² (one square metre only)	
9	1761.00 (one thousand seven hundred sixty one square metre)	Colour washing two coats over one coat of white washing with specially slacked and screened shell lime of approved quality and colour including cost and conveyance of colour pigments, brushes, all materials, labour charges and head load with initial lead and lift etc., complete.				1m ² (one square metre only)	